

GG251-14

807.5

Proponent: Barry Greive, representing Target Corporation (barry.greive@target.com)

Revise as follows:

807.5 Special inspections for sound levels. An approved agency, funded by the building owner, shall furnish report(s) of test findings indicating that the sound level results are in compliance with this section, applicable laws and ordinances, and the construction documents. Discrepancies shall be brought to the attention of the design professional and *code official* prior to the completion of that work. A final testing report documenting required testing and corrections of any discrepancies noted in prior tests shall be submitted at a point in time agreed upon by the building owner, or building owner's agent, design professional, and the *code official* for purposes of demonstrating compliance.

Exception: Special Inspections and reports are not required for approved assemblies with an established sound transmission class (STC) rating.

Reason: Special inspections are not needed on assemblies that have already been tested and have an established sound rating. 807.6 has an exception and this should have also been carried over to this section since they are similar in nature, this will bring consistency to section 807. A similar proposal is being carried to 807.5 for consistency.

Cost Impact: Will not increase the cost of construction.

GG251-14 : 807.5 #2-GREIVE1111
